



Option 1 - Plan

Golden Beach WSUD

Earnshaw Street Basin Landscape Concepts







Option 2 - Plan

Golden Beach WSUD
 Earnshaw Street Basin Landscape Concepts





Section A-A



Section B-B



Plan

Golden Beach WSUD
 Gregory Street Basin Landscape Concepts







Plan

Golden Beach WSUD
Wills Avenue Basin Landscape Concepts





Section C-C



Section D-D


Summary of Golden Beach basins

- Earshaw Street basin - most feasible
 - Good open space available
 - Limited impact on vegetation – re-vegetation works will improve vegetation outcomes
 - Diversion point feasible in park zone – limited impact on traffic
 - Good demonstration site and educational opportunities – link with park zone including interpretive signage
- Gregory Street basin – marginal
 - Highly constrained site - limited open space available
 - High impact on vegetation
 - Diversion required at road - costly
 - Coastal erosion issues of high concern
- Wills Ave basin – marginal
 - Vegetation impacts will occur but could be offset with revegetation works
 - Diversion can occur adjacent to footpath
 - Site topography will result in depths to approximately 3.5m to basin floor – visual integration and potential safety issues

Recommendations

- Complete detail functional designs for Earshaw Street basin
- Install a monitoring well to 3 m depth at the proposed Earshaw street basin
 - Monitor seasonal groundwater levels
 - Test in-situ pH and EC
 - Perform a falling head test
- Complete updated concept designs only for Gregory St and Wills Ave basins
 - Both sites are marginal due to site constraints and would not be recommended to be built at this stage

APPENDIX B - FEATURE SURVEY




EARNSHAW STREET

ESPLANADE

PUMICESTON CHANNEL

573
CG5004

Scale 1:200 - Lengths are in Metres.



Client: **DESIGN FLOW**
CONTOUR AND DETAIL SURVEY
 Earnshaw Street outfall
 Golden Beach Esplanade & Water Front
 PARISH: **BRIBIE** COUNTY: **Canning**
 Plan No: 6134DET Sheet 1/3 Scale: **1:200@A1**
 Prepared By: **TJ/AWJ** Date: **21/01/2014**

Skyline Surveyors
 Suite 8, Dwyer House
 258 Nicklin Way
 WARANA QLD 4575
 PHONE: 07 5493 4877
 FAX: 07 5493 4899

Note: Levels are to AHD Derived from PSM11219
 Services shown hereon have been located where possible by field survey.
 Prior to any demolition, excavation or construction on the site, the relevant authority should be contacted for possible location of further underground services and detailed locations of all services.

LEGEND

— SW —	STORM WATER	●	FIRE HYDRANT	⊗	ELECTRICITY PILLAR
— S —	SEWER MAIN	⊕	SIGN	⊙	TELECOMMUNICATIONS MARKER
— G —	GAS MAIN	⊙	PALM TREE	⊕	GAS LINE MARKER
— W —	WATER MAIN	⊙	TREE	⊕	WATER LINE MARKER
— C —	COMMUNICATION CABLES	⊕	WATER METER	⊕	STORMWATER M/H
— T —	TELSTRA CONDUIT	⊕	WATER METER	⊕	WATER VALVE
— E —	ELECTRICITY	⊕	SURVEY STN	⊕	SEWER MANHOLE
		⊕	PERMANENT SURVEY MARK	⊕	TRAFFIC LIGHTS
		⊕	POWER POLE	⊕	TRAFFIC SIGNAL CONTROL BOX
		⊕	STREET LIGHT	⊕	TELSTRA PIT
		⊕	ELECTRICITY MARKER	⊕	

GREGORY STREET


ESPLANADE

PUMICESTON CHANNEL

573

CG5004

Scale 1:200 - Lengths are in Metres.



Client: **DESIGN FLOW**
CONTOUR AND DETAIL SURVEY
 Gregory Street outfall
 Golden Beach Esplanade & Water Front
 PARISH: **BRIEBIE** COUNTY: **Canning**
 Plan No: **6134 DET Sheet 2/3** Scale: **1:200@A1**
 Prepared By: **TJ/AWJ** Date: **21/01/2014**



Suite 8, Dayyer House
 256 Nicklin Way
 WARANA QLD 4575
 PHONE 07 5493 4877
 FAX 07 5493 4899

Note: Levels are to AHD Derived from PSM11219
 Services shown hereon have been located where possible by field survey.
 Prior to any demolition, excavation or construction on the site, the relevant authority should be contacted for possible location of further underground services and detailed locations of all services.

LEGEND					
	STORM WATER		FIRE HYDRANT		ELECTRICITY PILLAR
	SEWER MAIN		SIGN		TELECOMMUNICATIONS MARKER
	GAS MAIN		PALM TREE		GAS LINE MARKER
	WATER MAIN		TREE		WATER LINE MARKER
	COMMUNICATION CABLES		WATER METER		STORMWATER M/H
	TELSTRA CONDUIT		SURVEY STN		WATER VALVE
	ELECTRICITY		PERMANENT SURVEY MARK		SEWER MANHOLE
			POWER POLE		TRAFFIC LIGHTS
			STREET LIGHT		TRAFFIC SIGNAL CONTROL BOX
			ELECTRICITY MARKER		TELSTRA PIT


WILLS AVENUE

ESPLANADE


ESPLANADE

PUMICESTON CHANNEL

573



Scale 1:200 - Lengths are in Metres.



Client: **DESIGN FLOW**
CONTOUR AND DETAIL SURVEY
 Wills Ave outfall
 Golden Beach Esplanade & Water Front

PARISH: **BRIBIE** COUNTY: **Canning**

Plan No: 6134DET Sheet 3/3 Scale: **1:200@A1**
 Prepared By: **TJ/AWJ** Date: **21/01/2014**

Skyline Surveyors

Suite 8, Dwyer House
 256 Nicklin Way
 WARANA QLD 4575

PHONE: 07 5493 4877
 FAX: 07 5493 4899

Note: Levels are to AHD Derived from PSM11219

Services shown hereon have been located where possible by field survey.

Prior to any demolition, excavation or construction on the site, the relevant authority should be contacted for possible location of further underground services and detailed locations of all services.

LEGEND

— SW —	STORM WATER	●	FIRE HYDRANT	⊕	ELECTRICITY PILLAR
— S —	SEWER MAIN	●	SIGN	⊕	TELECOMMUNICATIONS MARKER
— G —	GAS MAIN	●	PALM TREE	⊕	GAS LINE MARKER
— W —	WATER MAIN	●	TREE	⊕	WATER LINE MARKER
— T —	TELSTRA CONDUIT	●	WATER METER	⊕	STORMWATER M/H
— E —	ELECTRICITY	●	▲	⊕	WATER VALVE
		●	▲	⊕	SEWER MANHOLE
		●	▲	⊕	TRAFFIC LIGHTS
		●	▲	⊕	TRAFFIC SIGNAL CONTROL BOX
		●	▲	⊕	TELSTRA PIT

APPENDIX C - PIEZOMETER INSTALLATION AND GROUNDWATER
MONITORING

13 May 2014

Project No. 147633012-001-L-Rev0

Mr. Cory Josland
Sunshine Coast Council
Lock Bag 72
Sunshine Coast Mail Centre
NAMBOUR QLD 4560

Email: cory.josland@sunshinecoast.qld.gov.au

PIEZOMETER INSTALLATION AND GROUNDWATER MONITORING – GOLDEN BEACH

Dear Cory

1.0 INTRODUCTION

Golder Associates Pty Ltd (Golder) was commissioned by the Sunshine Coast Council (SCC), to install a piezometer (ST1) and undertake groundwater quality monitoring at Golden Beach, Caloundra. We are pleased to present the installation details and water quality monitoring results at the above site.

2.0 METHODOLOGY

A single piezometer (ST1) was installed using a 4WD mounted Drill Rig. The construction of the standpipe is detailed on the attached borehole report with the installation location shown on Figure 1.

Following installation a falling head test was performed on 20 March 2014 at high tide. Water level was recorded at regular intervals following twenty litres of water being poured into the piezometer. The results of the water level and time interval are presented in Table 1.

Additional water quality monitoring was undertaken at ST1 as requested by SCC. A total of 5 groundwater monitoring events were undertaken between 20 March 2014 and 7 May 2014.

Monitoring consisted of recording standing water level, salinity, pH, conductivity, redox, dissolved oxygen and temperature (refer to Table 2). Water samples were tested in the field using an Aquaread 'Aquaread' AP 2000-D model water quality analyser. In-situ groundwater testing was performed in accordance with the Department of Environment and Heritage Protection *Monitoring and Sampling Manual 2009* Version 2 September 2010.

All works outlined above was undertaken in the presence of or by an experienced environmental scientist from Golder.

3.0 GROUNDWATER RESULTS

A summary of groundwater monitoring results from all events are presented below Table 1 and Table 2.



Table -1: ST1 Falling Head Test Results (20 March 2014)

Test 1 – 11:05am		Test 2 – 11:15am	
Volume of Water	20 Litres	Volume of Water	20 Litres
Time (seconds)	Depth to water (mm)	Time (seconds)	Depth to water (mm)
0	2520	0	2380
10	2550	10	2470
20	2560	20	2520
30	2560	30	2550
40	2565	40	2550
50	2565	50	2550
60	2570	60	2550
70	2570	70	2555
80	2570	80	2555
90	2570	90	2560
100	2570	100	2560
110	2575	110	2560
120	2580	120	2560
130	2580	130	2560
140	2580	140	2565
150	2580	150	2565
160	2580	160	2565
170	2580	170	2565
180	2580	180	2565
190	2580	190	2565
200	2580	200	2565
210	2580	210	2565
220	2580	220	2565
230	2580	230	2565
240	2580	240	2565
250	2580	250	2565
260	2580	260	2565
270	2580	270	2565
280	2580	280	2565
290	2580	290	2565
300	2580	300	2565
310	2580	310	2565
320	2580	320	2565
330	2580	330	2565
340	2580	340	2565
350	2580	350	2565
360	2580	360	2570
370	2580	370	2570
380	2580	380	2570
390	2580	390	2570
400	2580	400	2570
410	2580	410	2570
420	2580	420	2570
430	2580	430	2570
440	2580	440	2570
450	2580	450	2570
460	2580	460	2570


Table -2: ST1 Water Quality Monitoring Results

Sampling Location										
Location	Date	Sampling Time	Tide	Water Level (RL m AHD)	pH	Conductivity (µs)	Salinity (PPT)	Redox (MV)	DO (mg/L)	Temp
ST1	20/03/2014	10:45am	High @ 10:45am - 1.59m	0.247	6.5	309	0.13	-	-	25.7
ST1	31/03/2014	8:00am	High @ 8:17am - 1.84m	0.594	6.6	266	0.13	66.8	3.36	25.5
ST1	31/03/2014	2:00pm	Low @ 2:27pm - 0.15m	0.407	6.5	296	0.15	39.6	3.21	25.8
Adjacent surface water	31/03/2014	8:30am	High @ 8:17am - 1.84m	-	6.1	58100	29.15	51.1	7.52	26.0
ST1	23/04/2014	3:30pm	High @ 3:25pm - 1.80m	0.451	6.6	463	0.23	42.1	4.10	25.4
ST1	05/5/2014	12.30pm	High @ 12.32pm - 1.60m	0.237	7.2	155	0.05	81.1	5.2	24.6

4.0 CLOSURE

Should you require any further information please contact the undersigned. We draw your attention to the document Limitations, attached.

GOLDER ASSOCIATES PTY LTD



Daniel Joyce BSc. ENV. CEnvP (0291)
Senior Environmental Scientist

DJJ/IW/djj



Ian Wallace BSc (Agric)(Hons), MEnvMgt, CPSS
Senior Environmental Scientist

Attachments: Figure 1
Report of Borehole and Explanatory Notes
Limitations
Invoice

j:\2014\contam\147633012 - scc-stormwater - golden beach\correspondence out\147633012-001-l-rev0.docx



**STORMWATER,
GOLDERN BEACH ESPLANADE**

SUNSHINE COAST COUNCIL

SITE PLAN



LEGEND

⊕ Standpipe Location

COPYRIGHT

Base map data Copyright MapInfo Australia Pty Ltd.
Aerial Photography Copyright NearMap Pty Ltd.
Image dated 03 November 2013

SCALE



1:400 (at A3)

DATUM GDA 94, PROJECTION MGA Zone 56

PROJECT: 147633012
DATE: 13 MAY 2014
DRAWN: BAL
CHECKED: DJ

FIGURE 1



Information contained on this drawing is the copyright of Golder Associates Pty. Ltd. Unauthorised use or reproduction of this plan either wholly or in part without written permission infringes copyright. © Golder Associates Pty. Ltd.



REPORT OF BOREHOLE: BH1

SHEET: 1 OF 1

CLIENT: Sunshine Coast Council
 PROJECT: Stormwater
 LOCATION: Golden Beach Esplanade
 JOB NO: 147633012

COORDS: 512099.0 m E 7034005.0 m N MGA94 56
 SURFACE RL: 2.15 m DATUM: AHD
 INCLINATION: -90°
 HOLE DIA: 50 mm HOLE DEPTH: 3.00 m

DRILL RIG:
 CONTRACTOR: Contract Drilling
 LOGGED: DJJ DATE: 19/3/14
 CHECKED: LG DATE: 7/5/14

Drilling			Sampling			Field Material Description				
METHOD	PENETRATION RESISTANCE	WATER	DEPTH (metres)	DEPTH RL	SAMPLE OR FIELD TEST	RECOVERED GRAPHIC LOG	USCS SYMBOL	SOIL/ROCK MATERIAL DESCRIPTION	MOISTURE CONDITION CONSISTENCY DENSITY	PIEZOMETER DETAILS
			-1.0							
			-0.5							
			0.0	2.15 0.70 2.05				SAND fine to medium grained, pale yellow, trace organics no organics		RL 2.837 Stickup RL 2.149 Concrete Bentonite plug Backfill D D-M M Slotted Screen Sand filter pack W RL -0.583
			0.5							
			1.0							
			1.5							
			2.0							
			2.5							
			3.0	-0.85				END OF BOREHOLE @ 3.00 m TARGET DEPTH GROUNDWATER MONITORING WELL INSTALLED		
			3.5							
			4.0							

GAP 8_0713 LIB:GLB Log GAP NON-CORED FULL PAGE 147633012.GPJ <<DrawingFile>> 07/05/2014 13:09 8.30.003 Datagel Tools

This report of borehole must be read in conjunction with accompanying notes and abbreviations. It has been prepared for environmental purposes only, without attempt to consider geotechnical properties or the geotechnical significance of the materials encountered. As such it should not be relied upon for geotechnical purposes.

GAP gINT FN. F01d
RL3

DRILLING/EXCAVATION METHOD


AS*	Auger Screwing	RD	Rotary blade or drag bit	NQ	Diamond Core - 47 mm
AD*	Auger Drilling	RT	Rotary Tricone bit	NMLC	Diamond Core - 52 mm
*V	V-Bit	RAB	Rotary Air Blast	HQ	Diamond Core - 63 mm
*T	TC-Bit, e.g. ADT	RC	Reverse Circulation	HMLC	Diamond Core - 63mm
HA	Hand Auger	PT	Push Tube	BH	Tractor Mounted Backhoe
ADH	Hollow Auger	CT	Cable Tool Rig	EX	Tracked Hydraulic Excavator
DTC	Diatube Coring	JET	Jetting	EE	Existing Excavation
WB	Washbore or Bailer	NDD	Non-destructive digging	HAND	Excavated by Hand Methods

PENETRATION/EXCAVATION RESISTANCE

- L Low resistance.** Rapid penetration possible with little effort from the equipment used.
- M Medium resistance.** Excavation/possible at an acceptable rate with moderate effort from the equipment used.
- H High resistance** to penetration/excavation. Further penetration is possible at a slow rate and requires significant effort from the equipment.
- R Refusal or Practical Refusal.** No further progress possible without the risk of damage or unacceptable wear to the digging implement or machine.

These assessments are subjective and are dependent on many factors including the equipment power, weight, condition of excavation or drilling tools, and the experience of the operator.

WATER

	Water level at date shown		Partial water loss
	Water inflow		Complete water loss

GROUNDWATER NOT OBSERVED The observation of groundwater, whether present or not, was not possible due to drilling water, surface seepage or cave in of the borehole/test pit.

GROUNDWATER NOT ENCOUNTERED The borehole/test pit was dry soon after excavation. However, groundwater could be present in less permeable strata. Inflow may have been observed had the borehole/test pit been left open for a longer period.

SAMPLING AND TESTING

SPT	Standard Penetration Test to AS1289.6.3.1-2004
4,7,11 N=18 30/80mm	4,7,11 = Blows per 150mm. N = Blows per 300mm penetration following 150mm seating Where practical refusal occurs, the blows and penetration for that interval are reported
RW	Penetration occurred under the rod weight only
HW	Penetration occurred under the hammer and rod weight only
HB	Hammer double bouncing on anvil
DS	Disturbed sample
BDS	Bulk disturbed sample
G	Gas Sample
W	Water Sample
FP	Field permeability test over section noted
FV	Field vane shear test expressed as uncorrected shear strength (s_v = peak value, s_r = residual value)
PID	Photoionisation Detector reading in ppm
PM	Pressuremeter test over section noted
PP	Pocket penetrometer test expressed as instrument reading in kPa
U63	Thin walled tube sample - number indicates nominal sample diameter in millimetres
WPT	Water pressure tests
DCP	Dynamic cone penetration test
CPT	Static cone penetration test
CPT _u	Static cone penetration test with pore pressure (u) measurement






















Ranking of Visually Observable Contamination and Odour (for specific soil contamination assessment projects)

R = 0	No visible evidence of contamination	R = A	No non-natural odours identified
R = 1	Slight evidence of visible contamination	R = B	Slight non-natural odours identified
R = 2	Visible contamination	R = C	Moderate non-natural odours identified
R = 3	Significant visible contamination	R = D	Strong non-natural odours identified

ROCK CORE RECOVERY

TCR = Total Core Recovery (%)	SCR = Solid Core Recovery (%)	RQD = Rock Quality Designation (%)
$= \frac{\text{Length of core recovered}}{\text{Length of core run}} \times 100$	$= \frac{\sum \text{Length of cylindrical core recovered}}{\text{Length of core run}} \times 100$	$= \frac{\sum \text{Axial lengths of core} > 100 \text{ mm}}{\text{Length of core run}} \times 100$


METHOD OF SOIL DESCRIPTION USED ON BOREHOLE AND TEST PIT REPORTS

<table border="0"> <tr><td></td><td>FILL</td></tr> <tr><td></td><td>GRAVEL (GP or GW)</td></tr> <tr><td></td><td>SAND (SP or SW)</td></tr> <tr><td></td><td>SILT (ML or MH)</td></tr> </table>		FILL		GRAVEL (GP or GW)		SAND (SP or SW)		SILT (ML or MH)	<table border="0"> <tr><td></td><td>CLAY (CL, CI or CH)</td></tr> <tr><td></td><td>ORGANIC SOILS (OL or OH or Pt)</td></tr> <tr><td></td><td>COBBLES or BOULDERS</td></tr> </table>		CLAY (CL, CI or CH)		ORGANIC SOILS (OL or OH or Pt)		COBBLES or BOULDERS
	FILL														
	GRAVEL (GP or GW)														
	SAND (SP or SW)														
	SILT (ML or MH)														
	CLAY (CL, CI or CH)														
	ORGANIC SOILS (OL or OH or Pt)														
	COBBLES or BOULDERS														

Combinations of these basic symbols may be used to indicate mixed materials such as sandy clay.

CLASSIFICATION AND INFERRED STRATIGRAPHY

Soil and Rock is classified and described in Reports of Boreholes and Test Pits using the preferred method given in AS1726 – 1993, (Amdt1 – 1994 and Amdt2 – 1994), Appendix A. The material properties are assessed in the field by visual/tactile methods.



MOISTURE CONDITION

AS1726 - 1993

Symbol	Term	Description
D	Dry	Sands and gravels are free flowing. Clays & Silts may be brittle or friable and powdery.
M	Moist	Soils are darker than in the dry condition & may feel cool. Sands and gravels tend to cohere.
W	Wet	Soils exude free water. Sands and gravels tend to cohere.

CONSISTENCY AND DENSITY

AS1726 - 1993

Symbol	Term	Undrained Shear Strength	Symbol	Term	Density Index %	SPT "N" #
VS	Very Soft	0 to 12 kPa	VL	Very Loose	Less than 15	0 to 4
S	Soft	12 to 25 kPa	L	Loose	15 to 35	4 to 10
F	Firm	25 to 50 kPa	MD	Medium Dense	35 to 65	10 to 30
St	Stiff	50 to 100 kPa	D	Dense	65 to 85	30 to 50
VSt	Very Stiff	100 to 200 kPa	VD	Very Dense	Above 85	Above 50
H	Hard	Above 200 kPa				

In the absence of test results, consistency and density may be assessed from correlations with the observed behaviour of the material.

SPT correlations are not stated in AS1726 – 1993, and may be subject to corrections for overburden pressure and equipment type.



LIMITATIONS

This Document has been provided by Golder Associates Pty Ltd ("Golder") subject to the following limitations:

This Document has been prepared for the particular purpose outlined in Golder's proposal and no responsibility is accepted for the use of this Document, in whole or in part, in other contexts or for any other purpose.

The scope and the period of Golder's Services are as described in Golder's proposal, and are subject to restrictions and limitations. Golder did not perform a complete assessment of all possible conditions or circumstances that may exist at the site referenced in the Document. If a service is not expressly indicated, do not assume it has been provided. If a matter is not addressed, do not assume that any determination has been made by Golder in regards to it.

Conditions may exist which were undetectable given the limited nature of the enquiry Golder was retained to undertake with respect to the site. Variations in conditions may occur between investigatory locations, and there may be special conditions pertaining to the site which have not been revealed by the investigation and which have not therefore been taken into account in the Document. Accordingly, additional studies and actions may be required.

In addition, it is recognised that the passage of time affects the information and assessment provided in this Document. Golder's opinions are based upon information that existed at the time of the production of the Document. It is understood that the Services provided allowed Golder to form no more than an opinion of the actual conditions of the site at the time the site was visited and cannot be used to assess the effect of any subsequent changes in the quality of the site, or its surroundings, or any laws or regulations.

Any assessments made in this Document are based on the conditions indicated from published sources and the investigation described. No warranty is included, either express or implied, that the actual conditions will conform exactly to the assessments contained in this Document.

Where data supplied by the client or other external sources, including previous site investigation data, have been used, it has been assumed that the information is correct unless otherwise stated. No responsibility is accepted by Golder for incomplete or inaccurate data supplied by others.

Golder may have retained subconsultants affiliated with Golder to provide Services for the benefit of Golder. To the maximum extent allowed by law, the Client acknowledges and agrees it will not have any direct legal recourse to, and waives any claim, demand, or cause of action against, Golder's affiliated companies, and their employees, officers and directors.

This Document is provided for sole use by the Client and is confidential to it and its professional advisers. No responsibility whatsoever for the contents of this Document will be accepted to any person other than the Client. Any use which a third party makes of this Document, or any reliance on or decisions to be made based on it, is the responsibility of such third parties. Golder accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this Document.

APPENDIX D - DESIGN DRAWINGS

EARNSHAW STREET - GOLDEN BEACH

INFILTRATION BASIN



DWG No	DESCRIPTION
D0001	SITE LOCALITY PLAN AND DRAWING LIST
D0002	NOTES
D0003	DEMOLITION PLAN
D0101	GENERAL ARRANGEMENT PLAN
D0102	SECTIONS AND DIVERSION PIT DETAILS
D0103	OUTFALL AND CONCRETE DETAILS
D0301	COVER SHEET
D0302	LANDSCAPE PLAN
D0303	LANDSCAPE DETAILS



Drawn	BLH	Verified	GAJ	Tod Consulting Draw No.
Designed	BLH	Checked	GAJ	
Approved	Douglas Reynolds	Approved	D Reynolds	13671-D0001
Supplied	Douglas Reynolds	Date	23/07/14	

A1	D	C 22/07/14	FINAL NOT FOR CONSTRUCTION ISSUED FOR APPROVAL	REC. APPR.	PSM No (AND) RL SURVEYED	111219 236	DRAWN	BLH	07/2014
	B	A 01/07/14							

INFRASTRUCTURE SERVICES
TRANSPORT INFRASTRUCTURE MANAGEMENT
CALOUNDRA OFFICE @ 1 Orman Avenue, Caloundra,
 Mail Locked Bag 72, Sunshine Coast Mail Centre, Nambour, QLD 4560
 Phone: (07) 547 5717 | info@sunshinecoastinfrastructure.com.au



EARNSHAW ST - GOLDEN BEACH
PROPOSED INFILTRATION BASIN
SITE LOCALITY PLAN
AND DRAWING LIST

Project Number:
24228

Sheet No. - Revision No.
D0001 . C

GENERAL NOTES :

1. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE
2. PRIOR TO COMMENCING WORK, THE CONTRACTOR SHALL PROVIDE TO THE SUPERINTENDENT A COPY OF THE CONSTRUCTION PROGRAM DETAILING THE DATES OF COMMENCEMENT AND COMPLETION FOR EACH STAGE.
3. PRIOR TO COMMENCING WORK, THE CONTRACTOR SHALL PREPARE AND FORWARD TO THE SUPERINTENDENT A REPORT ON THE CONDITION OF EXISTING INFRASTRUCTURE IN THE VICINITY OF THE WORKS SITE. THE REPORT SHALL LIST THE LOCATION AND EXTENT OF ANY EXISTING DAMAGE. THE CONTRACTOR WILL BE HELD RESPONSIBLE FOR ALL DAMAGED ASSETS THAT ARE NOT REPAIRED PRIOR TO THE COMMENCEMENT OF WORKS.
4. PRIOR TO COMMENCING WORK, THE CONTRACTOR SHALL PREPARE AND FORWARD AN EROSION AND SEDIMENT CONTROL PLAN TO THE SUPERINTENDENT FOR APPROVAL. THE CONTRACTOR SHALL COMPLY WITH THIS PLAN AND AUGMENT AS REQUIRED DURING THE CONSTRUCTION PHASE.
5. ALL DIMENSIONS AND LEVELS ARE TO BE SITE CHECKED AND ANY DISCREPANCY REPORTED TO THE SUPERINTENDENT.
7. ANY VARIATION TO THE DETAILS SHOWN IN THE DRAWING MUST BE AUTHORISED BY THE SUPERINTENDENT PRIOR TO FABRICATION AND/OR CONSTRUCTION.
8. CONSTRUCTION WORK SHALL BE CARRIED OUT IN STRICT ACCORDANCE WITH THE HEALTH AND SAFETY ACT 2011.
9. ALL PROPRIETARY PRODUCTS SHALL BE INSTALLED IN STRICT ACCORDANCE WITH THE MANUFACTURERS RECOMMENDATIONS.
10. ALL REDUCED LEVELS AND FINISHED SURFACE LEVELS ARE IN METRES TO AUSTRALIAN HEIGHT DATUM.
11. THE CONTRACTOR SHALL VERIFY THE LOCATIONS OF ALL EXISTING SERVICES WITH THE RELEVANT AUTHORITIES BEFORE COMMENCING CONSTRUCTION.
12. ALL ASSETS MODIFIED OR DAMAGED BY THE PROPOSED WORKS SHALL BE REINSTATED TO THE SATISFACTION OF THE SUPERINTENDENT.
13. THE CONTRACTOR SHALL REMOVE ALL STRUCTURES, DEBRIS AND FENCES FROM THE SITE TO THE SATISFACTION OF THE SUPERINTENDENT.
14. THE CONTRACTOR SHALL NOTIFY THE SUPERINTENDENT PRIOR TO COMMENCEMENT OF DEMOLISHING ANY EXISTING STRUCTURES WITHIN THE SITE AREAS

INSPECTIONS

- THE CONTRACTOR SHALL REQUEST THAT THE SUPERINTENDENT ARRANGE INSPECTIONS BY THE DESIGN TEAM AT THE FOLLOWING MILESTONES:
1. INITIAL POT-HOLE SURVEY OF PIPE INVERT AT PROPOSED DIVERSION POINT.
 2. AT THE COMPLETION OF BULK EARTHWORKS AND ALL CIVIL STRUCTURES TO CONFIRM COMPLIANCE WITH DESIGN DRAWINGS (CONTRACTOR TO PROVIDE AS CONSTRUCTED SURVEY PRIOR TO THESE INSPECTIONS).

HIGH FLOW CONTINGENCIES

1. CONTINGENCIES TO MANAGE RISKS ASSOCIATED WITH FLOOD EVENTS DURING THE CONSTRUCTION PERIOD ARE REQUIRED.
2. ADEQUATE EROSION AND SEDIMENT CONTROLS MUST BE IN PLACE AT THE END OF EACH DAY AND THE SITE MUST BE STABILISED AGAINST SOIL EROSION AS SOON AS POSSIBLE.
3. ALL MACHINERY SHALL BE STORED ABOVE ACCEPTABLE FLOOD LEVELS AND A MECHANISM FOR DEWATERING THE CONSTRUCTION SITE MADE AVAILABLE.

EARTHWORKS

1. NOT WITHSTANDING THE LIMITS OF CUTTING AND FILLING SHOWN ON THE DRAWINGS, THE ACTUAL LIMITS SHALL BE DETERMINED ON SITE BY THE SUPERINTENDENT DURING CONSTRUCTION. SIMILARLY, THE FINISHED SURFACE LEVELS MAY BE ADJUSTED BY THE WRITTEN DIRECTION OF THE SUPERINTENDENT DURING CONSTRUCTION.
 2. THE EXISTING SURFACE IS TO BE CLEAR OF VEGETATION MATTER PRIOR TO THE START OF FILLING.
 3. PRIOR TO THE PLACEMENT OF ANY FILL, THE EXPOSED SUBGRADE SHALL BE COMPACTED IN ACCORDANCE WITH AS 1289 TO THE APPROVAL OF THE SUPERINTENDENT AND ANY SOFT SPOTS SHALL BE REMOVED AND REPLACED WITH APPROVED FILL AND COMPACTED.
 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DEWATERING OF ALL TRENCHES AND EXCAVATIONS.
 5. THE CONTRACTOR SHALL DISPOSE OF ANY EXCESS SPOIL AS DIRECTED BY THE SUPERINTENDENT.
- TOLERANCES**
1. FINISHED EARTHWORKS LEVELS MUST BE WITHIN 50mm OF THE DESIGN LEVEL.
 2. HYDRAULIC STRUCTURE LEVELS (EG PITS CREST, WEIRS) SHALL BE WITHIN 10mm OF DESIGN LEVELS.

CONCRETE:

1. CONCRETE WORKS TO BE IN ACCORDANCE WITH AS3600 CONCRETE STRUCTURES
2. CONCRETE STRENGTH, REINFORCEMENT COVER, SLUMP AND SURFACE FINISH SHALL BE AS FOLLOWS:

ITEM	EXPOSURE	f _c (MPa)/ AGGREGATE SIZE (mm)	RED COVER (mm) - ALL FACES	TARGET SLUMP (mm)	FINISH TO TOP SURFACE	COLOUR
PIT WALLS	U	S40/20	75	100	OFF FORM	NIL
KERBS	B2	S40/20	50	100	OFF FORM	NIL
PATHS	B2	S40/20	50	100	REFER LANDSCAPE ARCHITECT	NIL

3. CONCRETE TO BE VIBRATED. EXCEPT EXTRUDED KERBS & CHANNELS.
4. PROVIDE HOLES OR CHASES ONLY WHERE SHOWN ON STRUCTURAL DRAWINGS. OBTAIN PREP ENGINEER APPROVAL FOR ANY ADDITIONAL HOLES OR CHASES BEFORE CARRYING OUT WORK.
5. SUPPORT REINFORCEMENT ON PLASTIC CHAIRS AND SPACERS TO GIVE CORRECT CONCRETE COVER.
6. PROVIDE JOINTS WHERE SHOWN ON THE DRAWINGS. OBTAIN PREP ENGINEER APPROVAL FOR ANY JOINT CHANGES BEFORE CARRYING OUT WORK.
7. THE FACE OF ALL CONCRETE AGAINST WHICH NEW CONCRETE IS TO BE POURED SHALL BE THOROUGHLY SCABLED, CLEAN OFF DUST AND CONTAMINANTS BEFORE NEW POUR.
8. FORMWORK TO REMAIN IN POSITION FOR FOLLOWING MINIMUM TIMEFRAMES AFTER FINISHING OPERATIONS COMPLETE. UNLESS OTHERWISE NOTED:
 - SIDEFORMS: 18 HOURS AND COMPRESSIVE STRENGTH TO EXCEED 0.5 x f_c
 - CONCRETE STRENGTH TO BE PROVEN BY TESTING AND APPROVED BEFORE STRIPPING FORMWORK
9. CONCRETE TO BE CURED IN ACCORDANCE WITH AS3600 CONCRETE STRUCTURES (REFER CONCRETE NOTE 1); PREFERRED CURING METHOD:
 - COMMENCE CURING TOP SURFACE OF SLABS ONCE FINISHING OPERATIONS COMPLETE. COMMENCE CURING ALL OTHER SURFACES WITHIN 1 HOUR OF STRIPPING FORMWORK.
 - CURE CONCRETE UNDER PLASTIC, LAPPED AND TAPED. HOSE WITH WATER ONCE DAILY UNDER PLASTIC AND RETAPE.

MINIMUM CURING PERIODS:

- CURE TOP SURFACE OF SLABS: 7 DAYS DURATION
 - CURE ALL OTHER SURFACES: 7 DAYS DURATION
- REQUIRED CURING PERFORMANCE (CONTRACTORS RESPONSIBILITY): CRACKS IN CONCRETE (90 DAYS AFTER PLACEMENT) SHALL NOT EXCEED THE FOLLOWING LIMITS:
- DECORATIVE CONCRETE: NOT GREATER THAN 0.1mm (BARRELY VISIBLE).
 - ALL OTHER CONCRETE: 0.3mm (DURABILITY LIMIT). CONCRETE CRACKS EXCEEDING LIMIT MUST BE REPLACED OR REPAIRED. OBTAIN APPROVAL FOR REPAIR METHODS BEFORE COMMENCING WORK.

PROVISION FOR TRAFFIC

1. THE CONTRACTOR SHALL SUPPLY AND MAINTAIN TRAFFIC BARRICADES, WARNING SIGNS, FLASHING LIGHTS AND OTHER DEVICES REQUIRED BY THE SUNSHINE COAST COUNCIL TO PREVENT PUBLIC ACCESS ONTO THE WORKS AND TO PROTECT THE PUBLIC.
2. THE CONTRACTOR SHALL PROVIDE NECESSARY TRAFFIC CONTROL MEASURES TO FACILITATE THE WORKS. TRAFFIC CONTROL DEVICES SHALL CONFORM TO THE REQUIREMENTS OF THE DEPARTMENT OF TRANSPORT AND MAIN ROADS (TMR) - MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES AND SUCH OTHER ADDITIONAL STANDARDS AS MAY BE ISSUED BY TMR FROM TIME TO TIME.

REINFORCEMENT:

1. REINFORCEMENT SHALL CONFORM WITH AS4671 STEEL REINFORCING MATERIALS.
2. ALL REINFORCEMENT TO BE ACORN (AUSTRALIAN CERTIFICATION AUTHORITY FOR REINFORCING STEEL) CERTIFIED. THE DESIGN ENGINEER RESERVES THE RIGHT TO REQUEST ACORN CERTIFICATES AT ANY TIME.
3. REINFORCEMENT SHALL BE GRADE D5000 HOT ROLLED HIGH YIELD BARS TO AS 4671, U.N.O. WHERE 'R' BARS ARE SPECIFIED. THESE SHALL BE ROUND BARS GRADE R250N
4. DO NOT CUT REINFORCEMENT TO CLEAR PENETRATIONS, SLEEVES OR HD BOLTS. DISPLACE REINFORCEMENT SLIGHTLY AS NECESSARY AND PROVIDE CORRECT COVER TO THE PENETRATIONS, SLEEVES OR HD BOLTS.
5. REINFORCEMENT LAP SPICE LENGTHS (MILLIMETRES) (U.N.O. ON DRAWINGS)

BAR LOCATION	D5000 BAR DIAMETER (mm)			
	12	16	20	24
LAP LENGTH (mm)				
ALL OTHER BARS (BOTTOM STEEL, COLUMNS, WALLS)*	450	600	850	1200
WELDED MESH				1400
				1750

225mm LAP

DRAINAGE PITS AND PIPES

1. ALL PIPE PENETRATIONS IN PITS TO BE SEALED FROM BOTH SIDES
2. DRAINS TO BE INSPECTED AND APPROVED BY THE SUPERINTENDENT PRIOR TO BACK FILLING.
3. ALL CONSTRUCTED PIPEWORK SHALL BE FLUSHED AND CLEANED AT THE COMPLETION OF WORKS TO THE SUPERINTENDENT'S APPROVAL.
4. ALL PIPES SHALL BE MINIMUM 300mm DIAMETER UNLESS STATED OTHERWISE.
5. ALL PIPES DEEPER THAN 600mm SHALL BE INSTALLED WITH CRANKED GALVANISED STEEL JOINS.
6. ALL STORMWATER PIPES SHALL BE CLASS '2' - R.C.P. UNLESS NOTED OTHERWISE. BULK FILLING REQUIREMENTS SHALL BE IN STRICT ACCORDANCE WITH THE COUNCIL'S REQUIREMENTS.
7. THE STORMWATER PIPE CLASSSES HAVE BEEN DESIGNED FOR SERVICE LOADS ONLY AND THE CONTRACTOR SHALL ASSES ANTICIPATED CONSTRUCTION LOADS AND UPGRADE THE PIPE CLASSSES IF NECESSARY IN ACCORDANCE WITH AS 3722-1989.
8. ANY UNGRADE SHALL BE AT THE CONTRACTORS COST.
9. MINIMUM PIPE GRADES ARE TO COMPLY GENERALLY WITH AS 3600 NATIONAL PLUMBING AND DRAINAGE CODE PART 3 STORMWATER EXCEPT WHERE SPECIFICALLY Y NOTED.
9. CONCRETE TO BE M25 UNLESS NOTED OTHERWISE.

REHABILITATION

1. PRE-DISTURBANCE SOIL PROFILES AND COMPACTION LEVELS ARE TO BE REINSTATED
2. ALL DISTURBED AREAS ARE TO BE LEFT IN A STABLE CONDITION. SLOPES SHOULD BE STABILISED USING APPROPRIATE EROSION CONTROL MEASURES.
3. UPON COMPLETION OF WORKS, THE CONTRACTOR SHALL ENSURE THAT THE SITE IS CLEAN AND Tidy WITH ALL RUBBISH AND OTHER MATERIALS REMOVED TO THE SATISFACTION OF THE SUPERINTENDENT.

A1	REV. DATE	ISSUED FOR COMMENT	REV. DATE	ISSUED FOR COMMENT
B	01/10/14	FINAL NOT FOR CONSTRUCTION		
C	01/10/14	ISSUED FOR APPROVAL		
D	01/10/14	ISSUED FOR COMMENT		

PSM No	11/219
(AND) RL	236
SURVEYED	SCC
DRAWN	BLH
CHECKED	GAL
DATE	07/2014

REC. APPR.	
REVISIONS	

PROJECT NUMBER:	24228
SHEET NO. - REVISED	D0002 . C

INFRASTRUCTURE SERVICES
TRANSPORT INFRASTRUCTURE MANAGEMENT
CALINDRA OFFICE @ 1 Orman Avenue, Cairns, Queensland
 Mail Locked Bag 72, Sunshine Coast Centre, Nambour, QLD 4560
 Phone: (07) 549 2172 info@sunshinecoastinfrastructure.com.au

Sunshine Coast COUNCIL

TOD consulting engineers
 Sunshine Coast, 07 5449 9600, Mooloolah 07 4460 2337
 PO Box 61, Nambour, QLD 4560
 531 53 153 282 2330
www.todconsulting.com

Drawn: BLH
 Checked: BLH
 Approved: Doug Reynolds
 Date: 23/07/14

Vertical: G.A.L.
 Verified: D Reynolds
 RPEP No: 9072

Total Consulting Draw No: **13671-D0002**
 Revision: C